

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12, 1996

Walter C. Thoren
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-------------|---|-------------|-------------------------|
| 1. Public Land Survey | T | <u>42</u> N | R | <u>23</u> W | <u>B-1</u> & <u>B-2</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Recorded DEC 20 1996
at 2:00 o'clock PM
Lib. 8 Page 187
Walter C. Thoren
Delta County, Ill. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims B-1 [N1/4 COR S.6] B-2 [C1/4 COR S.6]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, M.P. DAVIS, in a field survey on 21 NOVEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 [N1/4 COR S.6] WILLIAM BURT, D.S. -1841 - WOOD POST (BIRCH 08°-N56°W-20 LINKS) (CEDAR 11°-N23°W-17 LINKS) D.A. BROTHERTON-1910-ID CORNER POSITION BY 'GLO' BT & NOTED NEW BT'S (TAMARACK 14°-S4°W-62 LINKS) (TAMARACK 12°-S61°W-66 LINKS) J.E. GINGRASS-1912-IN PLACE-NO NEW WIT'S NOTED

B-2 [C1/4 COR S.6] NOT SET IN ORIGINALS
NO RECORD EVIDENCE OF CORNER MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 [N1/4 COR S.6] FOUND IN PLACE A 3/4" IRON PIPE AT APPROX C/L INTERSECTION OF COUNTY ROADS E-W & SOUTH AND IN LINE WITH ANCIENT FARM FENCE LINE TO THE NORTH. NO EVIDENCE OF D.A. BROTHERTON'S 1910 BT'S FOUND. MEASUREMENTS TO ADJOINING CORNERS FIT REASONABLY WELL WITH THE RECORDS OF BROTHERTON. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

B-2 [C1/4 COR S.6] ESTABLISHED AT INTERSECTION OF N-S & E-W 1/4 LINES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 SET, OVER EXISTING MONUMENT, A 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE COR POSITION & RAISED TO GRADE W/A MON BOX.
5/8" X 18" REBARS W/A SURVEY CAP SURVEY MONUMENT SIGN POST NOTE: FARM FIELDS IN THE NW, NE & SE QUADRANTS AND VIABLE WIT'S IN THE SW QUADRANT
N45°W - 25.25' S45°W - 35.12' NORTH
N45°E - 22.00' S45°E - 34.60' 18.46' (TO FACE)

B-2 SET, 6" BELOW GRADE, A 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.
TAMARACK 9" SPRUCE 7" SURVEY MONUMENT SIGN POST
N56°E S72°E WEST
61.36' 84.72' 18.81' (TO FACE)



NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. DAVIS Date 12/12/96
Surveyor's Michigan License No. 16926