

MAR 21 1997

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12, 1996

Walter C. Thomas
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 42 NR 23 W C-9 & C-10
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims C-9 [NW COR S.29] C-10 [W1/4 COR S.29]

Recorded DEC 20 1996
at 2:00 o'clock PM
Liber 8 Page 158
Walter C. Thomas
Delta County, Mich. Reg. of Deeds

Register of Deeds Stamp & File Number

I, M.P. DAVIS, in a field survey on 04 DECEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- C-9 [NW COR S.29] E.C.MARTIN, D.S. - 1852 - WOOD POST (HEMLOCK 18°-S58°E-14 LINKS) (Y.BIRCH 08°-N40°W-04 LINKS)
NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT CORNER MONUMENTATION
 - C-10 [W1/4 COR S.29] E.C.MARTIN, D.S. - 1852 - WOOD POST (HEMLOCK 10°-S66°E-23 LINKS) (PIR 08°-N53°W-16 LINKS)
NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT REMONUMENTATION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- C-9 [NW COR S.29] NO CORNER EVIDENCE FOUND. MAINTAINING THE SPIRIT OF THE ORIGINAL SURVEY AND THE MANNER IN WHICH THIS CORNER WAS ORIGINALLY SET. REESTABLISHED CORNER POSITION ON A STRAIGHT LINE WITH AND SINGLE PROPORTIONATE DISTANCE BETWEEN THE NW COR'S OF SEC'S 20 & 32.
 - C-10 [W1/4 COR S.29] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION AT THE MIDPOINT BETWEEN SECTION CORNERS 1/2 MILE NORTH AND SOUTH.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-9 SET BERNTSEN AINB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.

MAPLE 06"	MAPLE 08"	MAPLE 09"	SURVEY MONUMENT SIGN POST	N-S WOODS ROAD
N15°W	S52°E	S37°W	WEST	EAST
9.43'	47.26'	14.18'	2.65' (TO FACE)	12'
 - C-10 SET BERNTSEN AINB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.

CEDAR 4"	MAPLE 12"	MAPLE 5"	MAPLE 13"	SURVEY MONUMENT SIGN POST
N44°W	N49°E	S20°E	S77°W	EAST
28.41'	29.95'	21/06'	37.19'	1.64' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/10/96
Surveyor's Michigan License No. 16926