

SURVEY & REMONUMENTATION COMMISSION

MAR 21 1997

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On 12/12, 1996

Walter C. Thoren
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 42 N R 23 W D-1 & D-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Recorded DEC 20 1996
at 2:00 o'clock PM
Liber 8 Page 190
Walter C. Thoren

Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims D-1 [N1/4 COR S.5] D-3 [N1/4 COR S.8]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4									
3			8	9	10	11	12						
4	7		8	9	10	11	12						
5													
6	18		17	16	15	14	13						
7													
8	19		20	21	22	23	24						
9													
10	30		29	28	27	26	25						
11													
12	31		32	33	34	35	36						
13													

I, M.P. DAVIS, in a field survey on 21 NOVEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 [N1/4 COR S.5] E.C.MARTIN, D.S. - 1852 - WOOD POST (CEDAR 13°-N76°E-21 LINKS) (FIR 07°-N58°W-25 LINKS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION.

D-3 [N1/4 COR S.8] E.C.MARTIN, D.S. - 1852 - WOOD POST (SUGAR 18°-S38°E-40 LINKS) (DEAD Y. BIRCH 12°-N38°W-40 LINKS)
M.S.McNABB-1913-ORIGINALS DESTROYED-SET FROM IMPROVEMENTS (TAMARACK 10°-S31°E-33')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 [N1/4 COR S.5] NO EVIDENCE OF CORNER FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN SECTION CORNERS 1/2 MILE EAST & WEST.

D-3 [N1/4 COR S.8] NO EVIDENCE OF McNABB'S 1913 CORNER OR HEMLOCK BT FOUND. REESTABLISHED CORNER POSITION FROM EXISTING IMPROVEMENTS (C/L COUNTY ROAD N-S & ANCIENT FENCE LINES, DOWN AND IN POOR CONDITION, E-W). ACCEPTED AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 SET 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MONUMENT BOX.

DRILL HOLE IN FIELD STONE	SPRUCE 05"	TAMARACK 04"	SPRUCE 06"	SURVEY MONUMENT SIGN POST
N28°W	N27°E	S18°E	38°W	NORTH
36.47'	55.02'	33.60'	35.00'	17.16' (TO FACE)

D-3 SET, 6" BELOW ROAD SURFACE, A 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.

BALSAM 08"	SPRUCE 12"	MAPLE 12"	BALSAM 07"	SURVEY MONUMENT SIGN POST
N60°W	N50°E	S68°E	S64°W	WEST
32.03'	63.82'	58.59'	43.22'	19.00' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis

Date 12/10/96

Surveyor's Michigan License No. 16926