

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 12/12, 1996
Walter C. Thomas
 Delta County Chairman

For corners in
DELTA
 (County)

Located In: Corner Code ##

- | | | |
|------------------------------------|-----------------------------|--------------------|
| 1. Public Land Survey | T <u>42</u> N R <u>23</u> W | E-11 & <u>E-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded **DEC 20 1996**
 at 2:00 o'clock PM
 Liber 8 Page 170
Walter C. Thomas
 Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims E-11 [NW COR S33] E-12 [W1/4 COR S.33]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on 12 NOVEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 [NW COR S.33] E.C.MARTIN, D.S. - 1852 - WOOD POST (HEMLOCK 15'-N70°E-12 LINKS) (CEDAR 12'-S42°W-10 LINKS)
 NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT MONUMENTATION.

E-12 [W1/4 COR S.33] E.C.MARTIN, D.S. - 1852 - WOOD POST (SPRUCE 15'-N38°E-16 LINKS) (SPRUCE 10'-S44°W-21 LINKS)
 NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 [NW COR S.33] FOUND IN PLACE BY PERSONS UNKNOWN A BUGGY AXEL & REMAINS OF A SQUARED CEDAR POST AT THE JCT OF ANCIENT FENCE LINES WEST & NORTH & FITS WELL WITH OTHER MONUMENTATION TO THE SOUTH AND AS THE EXISTING MONUMENT APPEARS TO BE ACCEPTED BY INTERESTED PROPERTY OWNERS WITHOUT DISPUTE I HAVE ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

E-12 [W1/4 COR S.33] FOUND IN PLACE, THIS DATE BY PERSONS UNKNOWN, A 1" IRON PIPE VERY NEAR THE MIDPOINT BETWEEN SECTION CORNERS N & S, NO OTHER EVIDENCE FOUND. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 SET, OVER EXISTING MON A BERNTSEN AINB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.

MAPLE 10"	MAPLE 10"	MAPLE 09"	SPRUCE 06"	SURVEY MONUMENT SIGN POST
N04°W	N57°E	S35°E	S72°W	NORTH
26.52'	8.02'	33.28'	42.77'	2.31' (TO FACE)

E-12 SET, OVER EXISTING MONUMENT A 5/8" X 18" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE COR POSITION.

PP	SURVEY MONUMENT SIGN POST	NOTE: OPEN FIELDS IN ALL FOUR QUADRANTS
S83°W	S86°E	NO OTHER WIT'S AVAILABLE
12.34' (TO FACE)	18.25' (TO FACE)	

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/10/96
 Surveyor's Michigan License No. 16926

