

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12, 1996

Walter C. Thomas
Acting Chairman

For corners in

DELTA

(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|-----------------------------|-------------------------|
| 1. Public Land Survey | T <u>42</u> N R <u>23</u> W | <u>I-6</u> & <u>I-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded DEC 20 1996
at 2:00 o'clock PM
Liber 8 Page 167
Walter C. Thomas
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims I-6 [W1/4 COR S14] I-7 [NW COR S.23]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6 [W1/4 COR S.14] E.C.MARTIN, D.S. - 1852 - WOOD POST (ASPEN 12°-542'E-17 LINKS) (FIR 08°-N18°W-18 LINKS)
NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT MONUMENTATION.

I-7 [NW COR S.23] E.C.MARTIN, D.S. - 1852 - WOOD POST - NO WIT'S GIVEN
T.OBRIEN-1988-1¹/₂" I.P. & SQUARED POST IN PLACE-REC'D LIBER 6 OF LCR'S PG 33 (SPRUCE 06-N41°E-86.80')(BOX ELDERS N88°W-23.55')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 [W1/4 COR S.14] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION ON A STRAIGHT LINE WITH SECTION CORNERS 1/2 MILE N & S AND IN LINE WITH ANCIENT FENCE LINES E & W. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

I-7 [NW COR S.23] FOUND IN PLACE A 1¹/₂" IRON PIPE AS DESCRIBED IN LIBER 6 OF LCR'S PAGE 33, SQUARED POST NOW DOWN & IN POOR CONDITION. ID CORNER FROM O'BRIENS SPRUCE BT, STILL GREEN. EXISTING MONUMENT FITS WELL WITH "GLO" TERRAIN CALLS TO MARSH EDGES E, W & S. ACCEPTED EXISTING MONUMENT AS THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 SET, 6" BELOW GRADE, A 5/8" X 18" REBAR W/A 3¹/₄" ALUM CAP STAMPED TO ID THE CORNER POSITION.

ELM 06"	SPRUCE 06"	CEDAR 10"	SPRUCE 5"	SURVEY MONUMENT SIGN POST
N17°W	N46°E	S63°E	S70°W	WEST
74.68'	66.34	45.43	48.60'	16.33' (TO FACE)

I-7 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE COR POSITION.

ELM 08"	ELM 09"	SPRUCE 06"	SURVEY MONUMENT SIGN POST	
N75°W	N14°W	N41°E	SOUTH	85.90'
20.12'	86.08'	72.75'	1.50' (TO FACE)	

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/10/96

Surveyor's Michigan License No. 16926