

LAUSING

ENG. / W.M.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta
(County)

Located In:

Corner Code #

LAND SURVEY SECTION

- 1. Public Land Survey T 43N R 22W 1-7 ✓
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on May 19, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-7. SE section corner of Section 15--Mich. Dept. of Conservation 1956--replaced as set by unknown surveyor, cedar post in place. Found evidence of tamarack stp. bottom as per: Gov't. field notes.

- 1956 NBT's. 10" cedar N58°W - 98 Lks.
- 10" soft maple N33°E - 59 Lks.
- Power pole - S26°E - 38 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-7. Found brass capped Conservation Department monument with pipe bent over and cap broken. Both Conservation Department NBT's in place with blazes healed over. Replaced broken monument with new DNR monument and marked two additional NBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7. DNR Monument.

- Nail & brass tag inside of { 6" apple - S10°W - 42.2 feet
- { P. pole - S50°E - 54.3 feet
- 1956 NBT's { 12" maple N45°E - 59 links.
- { 14" cedar N32°E - 98 links.

NOTE: My bearings to 1956 NTB's do not agree with 1956 record.

Signed by David B. Babbitt

Date 6-9-86

Surveyor's Michigan License No. 21558