

1. MICHIGAN LAND SURVEY \_\_\_\_\_ 20 T. 43N N. S., R. 22W E. W. C-7  
 2. PROPERTY CONTROLLING IN SECTION \_\_\_\_\_, T. \_\_\_\_\_ N. S., R. \_\_\_\_\_ E. W.  
 3. MISCELLANEOUS PROPERTY IN SECTION \_\_\_\_\_, T. \_\_\_\_\_ N. S., R. \_\_\_\_\_ E. W.  
 4. LOT NO. \_\_\_\_\_, RECORDED PLAT \_\_\_\_\_  
 5. PRIVATE CLAIMS \_\_\_\_\_

**DELTA  
CO.**

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 25, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-7. NW sec. cor. of Section 20.  
 Billy D. Buckler, Mich. Cons. Dept.  
 1" pipe w/4" brass cap.  
 12" soft maple - S10°W - 48 lks.  
 12" soft maple - N60°E - 33 lks.  
 9" y. birch - S30°E - 93 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-7. Found sq. scribed post with stump of soft maple cut low N67°E, 33 lks. and blazed and scribed 13" soft maple S86°W, 48 lks. (Record bearing S10W obviously in error.) Buckler's y. birch N.B.T. had been bulldozed out by road construction. (Found blazed stump beside road) Could not find any sign of pipe and brass cap. Set D.N.R. monument from two remaining N.B.T.'s (Soft maple stump and tree).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7. D.N.R. Monument  
 7" cedar N88°E - 15.9'  
 8" spruce N60°W - 22.5'  
 10" spruce S74°W - 22.9'  
 7" y. birch S60°E - 67.1'  
 (old N.B.T.)  
 13" s. maple S86°W - 31.8'  
 s. maple stp. N67°E - 21.8'

SIGNED BY David B. Babbitt DATE 2-11-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)