

1. Public Land Survey T 43N R 22W G-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**DELTA
CO.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 10/9, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1. NE corner of Section 4. Mich. DNR - 1972 1" iron pipe w/4" aluminum cap
 10" B. Spruce N30E 17.6'
 4" R. Maple N34W 6.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1. Found monument torn out by large balsam uprooted by wind. Re-set monument from 1972 N.B.T.'s and marked two new N.B.T.'s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1. 1" pipe, 4" alum. cap. 10" B. Spruce N30E 17.6' } Old
 4" R. Maple N34W 6.0' }
 8" R. Maple N30E 14.55' } New
 7" Cedar N61°E 27.9' }

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by David B. Babbitt Date 2-11-86

Surveyor's Michigan License No. RLS 21558