

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 43 N R 22W

DESCRIPTION OF CORNER Section Corner for Sections 9/10
16/15

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10-30-72 F. J. Bray

WITNESSES TO CORNER..... 9" R. Maple (S9) (NBT) N28°W, 9.7'



7" H. Maple (S10) (NBT) N53° E, 2.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners 1 mile to the north, east and west and 2 miles to the south. Blazed trees and down wood past near. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

11-15-72