

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Marquette
Delta
Alger
COUNTYS
22
T 44 N R 23 W
43

DESCRIPTION OF CORNER Town corner for T43N-R23W 36/31 T44N-R22W
T43N-R23W 1/6 T43N-R22W

CORNER MONUMENT 1 1/2"x30" iron pipe buried in west wheel track of woods road.

DATE MONUMENT PLACED AND WITNESSED June 13, 1972 F. J. Bray

WITNESSES TO CORNER..... 12" Hemlock (S.31) (NET) N50°E, 22.3'



18" Hemlock (S.36) (NET) N46°W, 30.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two hemlock stumps which Marcus McNabb noted as new B.T.s (Hemlock 16" N25°W 19.25') and (Hemlock 20" S46°E 30.75'). The bearing of stump to the southeast is in error but distance is good.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

8-11-72