

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY
T 43 N R 22 W

DESCRIPTION OF CORNER Section corner for Sections ^{3/2} 10/11

CORNER MONUMENT 1" iron pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 13, 1972 F. J. Bray

WITNESSES TO CORNER..... 9" Cedar (S.2) (NET) N67°E, 23.1'



11" R. Maple (S.10) (NET) S39°W, 33.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between the section corners one mile to the north, south and west and 1/4 corner 1 1/2 miles to the east. U. S. Forest Service tag near. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED


REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

8-11-72