

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 43 N R 22 W

DESCRIPTION OF CORNER Section corner for Sections $\frac{2}{1}$ ~~11~~/12

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 17, 1972

WITNESSES TO CORNER..... 6" B. Ash (S.2 NBT) N73°W, 6.0'



7" Cedar (S.1) (NBT) N85°E, 8.2'

6" B. Ash (S.12) (NBT) S37°E, 14.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between the section corners one mile to the north, two miles to the west and 1/4 corners one-half mile to the east and to the south.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED


REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

8-11-72