

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY

T 43 N R's 21 & 22 W


T43N- 1/6 T43W  
R22W 12/7 R21W

DESCRIPTION OF CORNER Section corner for Sections

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/4/71 F. J. Bray

WITNESSES TO CORNER..... 6" Cedar (S.7) (NBT) S28°E, 5.7'



12" Blazed & notched Cedar (NBT) S55°W, 3.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two wood points of rotted posts. Position checks with down rotted cedar to northeast with over-growth of faces and axe marks visible. Cedar to southwest with blaze and notches faces corner. Blaze approximately 50 years old.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE 12-9-71

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68