

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 43N R 22W

DESCRIPTION OF CORNER Section Corners 16/15
21/22

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-17-72 F. J. Bray

WITNESSES TO CORNER..... 8" Aspen (S 15) (NBT) N21° E, 4.7'



4" R. Maple (S22) (NBT) S 89° E 26.0'

4" Balsam (S22) (NBT) S8° E 9.2'

AND

12" Cedar Stump (NBT) N77° W 18.3'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by double proportionate measurement between section corners
1 mile to the north, east and south and $\frac{1}{4}$ corner $\frac{1}{2}$ mile to the west.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12-15-72