

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY  
T 43 N R 22 W

DESCRIPTION OF CORNER Section Corner for sections  $\frac{8}{9}$  17/16

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10-20-72 F. J. Bray

WITNESSES TO CORNER..... 9" R. Maple (S16) (NBT) S 82°E, 19.8'



7" Cedar (S16) (NBT) S14°E, 19.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between  
 $\frac{1}{4}$  corner  $\frac{1}{2}$  mile to the north and to the west and section corners 1 mile to  
the south and 2 miles to the east.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

11-15-72