

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY
T 43 N R 22 W

DESCRIPTION OF CORNER 1/4 corner for Sections $\frac{1}{12}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/3/71 F. J. Bray

WITNESSES TO CORNER..... 11" Cedar (1/4S) (NBT) N 28° E, 14.7'



9" Cedar (1/4S) (NBT) S 84° E, 15.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from down and rotted wood stake. Marcus McNabb, surveyor, witnessed this corner in 1923. White birch, N 35° W, 4.8' and east 43.0' of \emptyset of railroad grade were McNabb's witnesses. Birch to northwest has rotted bottom face and Forest Service location poster.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 9-21-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68