

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 43 & 42 N R 22 W

DESCRIPTION OF CORNER 34/35
3/2

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/17/71 F. J. Bray

WITNESSES TO CORNER..... 6" W. Birch (Twin) (s.3) (NBT) S 82° W, 15.1'



12" Cedar Stump (NBT) S 47° E, 13.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between the section corners one mile to the east and one mile to the west. Stream to the west and swamp edge to the north check well. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

9-20-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68