

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY

21


T 43 & 42 N R's 22 W

DESCRIPTION OF CORNER Town corner T43N T43N
R22W 36/31 R21W
T42N 1/6 T42N
R22W R21W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7/21/71 F. J. Bray

WITNESSES TO CORNER..... 6" Elm (S.1) (NBT) S 68° W, 4.4'



7" Y. Birch (S.31) (NBT) N 50° E, 11.5'

8" Elm (S.6) (NBT) S 51° E, 24.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two original B.T.s both are stumps approximately four-feet high and in poor condition. Scribe marks are faintly visible on weathered faces. Down fence corner two links to the north. Found by Survey crew.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

9-20-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68