

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 43 N R 22 W

DESCRIPTION OF CORNER 1/4 corner for Sections $\frac{25}{36}$

CORNER MONUMENT 1" iron pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7/30/71

WITNESSES TO CORNER..... 7" Elm (1/4S) (NBT) N 02° W, 7.0'



9" H. Maple (1/4S) (NBT) S 80° E, 15.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between the section corners to the east and to the west. Forest Service notes of 1937 noted wood post east of railroad grade in four-foot cut which check well. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 9-21-71
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68