

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY

T 43 N R's 22 & 23 W


T43N 13/18 T43N
R23W 24/19 R22W

DESCRIPTION OF CORNER Section corner for Sections

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/14/71 F. J. Bray

WITNESSES TO CORNER..... 7" Tamarack (S.19) (NBT) S65°E, 16.3'



6" Tamarack (S.18) (NBT) N28°E, 8.4'

8" Cedar stub with F.S. poster, S63°W, 3.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two old wood posts set from original B.T.s. Tamarack to northwest is down with burned lower face and notch. Tamarack to the southwest is a rotted stump which checks with bearing and distance of original field notes.

SURVEYOR'S SEAL

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12-9-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68