

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY
T 43 N R 22 W

DESCRIPTION OF CORNER Section corner for Sections $\frac{22}{23}$
 $\frac{27}{26}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/21/71

WITNESSES TO CORNER..... 22" W. Pine (NBT) N43°W, 4.9'



7" H. Maple (S.26) (NBT) S07°E, 20.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed in line with fence to the south and using Marcus McNabb's measurement to the corner to the north. McNabb found an iron pipe at this location in a survey in 1929. This area has been bulldozed and the pipe is missing. McIntyre, adjoining land owner, remembers the corner in this location.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 12-9-71
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68