

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 43 N R 22 W

DESCRIPTION OF CORNER Section corner for Sections $\frac{20}{21}$ / $\frac{29}{28}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/5/71 F. J. Bray

WITNESSES TO CORNER..... 8" Cedar stump (NBT) N82°E, 15.0'



6" Cedar (S.28) (NBT) S41°E, 17.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement between the section corners 1 mile to the north and to the east and the 1/4 corners 1/2 mile to the south and to the west. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12-9-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68