

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


DELTA COUNTY
T 43 N R 22 W

DESCRIPTION OF CORNER Section corner $\frac{11}{12}$
 $\frac{14}{13}$

CORNER MONUMENT 1/2-inch iron rod 14 inches long in road

DATE MONUMENT PLACED AND WITNESSED April 26, 1972

WITNESSES TO CORNER..... 9 Balsam (S.13) (NBT) S55°E 56.9'



7 Balsam (S.12) (NBT) N78°E 46.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by double proportionate measurement from the corners
1/2 mile to the north, one mile to the south, 1/2 mile to the east and one
mile to the west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 6-19-72
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68