

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43.. NR 22 W. . .

Delta COUNTY

DESCRIPTION OF CORNER . . . Section Corner Common to Sections 10, 11, 14, 15

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 14" Cedar . . . N 61° E . . . 66 links
Marked "S 11 NBT"

8" Cedar . . . S 26° E . . . 64 links
Marked "S 14 NBT"

10" Cedar . . . N 87° W . . . 22 links
Marked "S 10 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one Cedar B.T., poor condition.
Found overgrowth in Notch.
One Black Ash B.T. in place dead but solid, rotten inside.

Corner lies 30 links East of a small stream

Corner found by Forestry Division Survey Crew while making a partial re-survey of this township.

Corner placed and witnessed October 31, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 11/21/56
REGISTERED/LAND SURVEYOR