

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 22 W.

Delta COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 16-17-20-21

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	6" Cedar	N 50° E	6 links
		"S 16 NBT"	
	8" Cedar	N 81° W	47 links
		"S 17 NBT"	
	11" Cedar	S 21° W	30 links
		"S 20 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner.

Found very old cedar post. Numerous blazes east, west, north and south of Corner, Forest Service tag "1937".

Numerous cruisers names on cedar tree dating to 1916.

Distance east checks to 1/4 corner. Found by Forestry Division Survey Crew.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/5/52  
REGISTERED LAND SURVEYOR