

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 22 W.

Delta COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 17-18-19-20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	12" Soft Maple	S 10° W	48 links
		"S 19 NBT"	
	12" Soft Maple	N 60° E	33 links
		"S 17 NBT"	
	9" Y. Birch	S 30° E	93 links
		"S 20 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from two hemlock stump bottoms bearing N 35° W 27 links and S 45° E 18 links. Distance checks very good in all four directions.

Found many old line blazes east of corner. Found post 41 links west and 1.14 chs. south set as approximate corner by unknown persons.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/5/57
REGISTERED LAND SURVEYOR