

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 22 W.

Delta COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec.'s 17-20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Cedar N 22° E 30 links
"1/4 S NBT"

7" Soft Maple S 58° E 29 links
"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner midway and on line between two section corners.

No evidence of original B.T.'s. Found post set for approximate 1/4 corner by Forest Service 37 links east and 67 links south of 1/4 corner.

1/4 corner lies 65 links west of old logging road N-S. Placed location poster 24 chs. east on woods road.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/5/57
REGISTERED LAND SURVEYOR