

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43N</u> N. S., R. <u>22W</u> E. W.	<u>H-8, H-7</u>
2. PROPERTY CONTROL-22 ING IN SECTION _____	T. <u>43N</u> N. S., R. <u>22W</u> E. W.	<u>9, 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-8 - Center 1/4 Cor. of Sec. 22; not previously established.
- H-7 - N 1/4 Cor. of Sec. 22; wood post - Cedar 6" - N35°W - 5 Lks.; Cedar 10" - S35°E - 7 Lks.
- 9 - E 1/16 Cor. on the E-W 1/4 line of Sec. 22; not previously established.
- 16 - East 1/16 Cor. on the South Sec. line of Sec. 22.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-8 - Set at the intersection of the N-S & E-W 1/4 lines of Sec. 22.
- H-7 - Set M.P.O.L. between the N.E. and N.W. Sec. Cors. of Sec. 22. Some cedar stumps in the area but could not identify any as O.B.T.S.
- 9 - Set M.P.O.L. between the Ctr. of Sec. and the E. 1/4 Cor. of Sec. 22.
- 16 - Set M.P.O.L. between the S. 1/4 Cor. and the S.E. Sec. Cor. of Sec. 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-8 - D.N.R. Mon.; 9" Sugar Maple - N45°W - 36.1'; 6" Sugar Maple - N25°E - 18.5'; 4" Sugar Maple - S40°W - 25.0'; 8" Sugar Maple - S22°E - 30.5'
- H-7 - D.N.R. Mon.; 7" Cedar - N15°W - 31.7'; 6" Cedar - N16°E - 28.1'; 9" Cedar - S42°E - 30.6'; 8" Cedar - S9°W - 30.6'
- 9 - D.N.R. Mon.; 8" Cedar - S63°E - 33.3'; 5" Cedar - N72°W - 22.0'; 5" Balsam - N62°E - 8.3'; 4" Cedar - S4°W - 39.2'
- 16 - D.N.R. Mon.; 13" Y. Birch - S77°W - 44.9'; 4" Sugar Maple - N23°W - 19.3'; 4" Sugar Maple - S5°W - 18.2'; 10" Sugar Maple - N68°E - 3.5'

SIGNED BY David B. Babbitt DATE 3-7-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: