

**LAND CORNER RECONSTRUCTION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43N</u> N. S., R. <u>22W</u> E. W.	<u>H-9 &amp; I-9</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-9 - S 1/4 Corner of Section 22; Marcus McNabb - 1929 - No description of Cor. Mon. N.B.T.s- Elm - 6" - N55°E 50'; Basswood 6" - S36°W - 43.5'.

I-9 - S.E. Sec. Cor. of Sec. 22; Frank Bray R.L.S. 9-21-71 - set D.N.R. Mon. 22" W. Pine - N43°W - 4.9'; 7" H. Maple - S7°E - 20.5'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-9 - Set on line between the S.E. and S.W. Sec. Cors. of Sec. 22 and 2646.7' Easterly of said S.W. Sec. Cor. as recorded in a record of survey by Marcus McNabb in 1929. This falls exactly in line with an old fence line South. McNabbs N.B.T.s are gone.

I-9 - Found D.N.R. Mon. as set by Frank Bray in 1971. His W. Pine N.B.T. is gone. Re-witnessed Mon. as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 - 1" pipe 4" aluminum cap; 5" Cedar - N39°W - 75.3'; 10" R. Maple - N16°E - 55.6'; 14" Sugar Maple - S5°W - 57.4'; 6" Sugar Maple - S34°W - 64.1'.

I-9 - 1" pipe 4" aluminum cap; 6" Y. Birch - N54°E - 87.9'; 12" Y. Birch - S77°E - 51.5'; power pole - N5°E - 21.6'.

SIGNED BY

*David B. Babbitt*

DATE

3-7-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: