

185

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta (County) Located In: Corner Code //
1. Public Land Survey T 43N R 22W K-4, K-5, K-6
2. Property Controlling in Section S 13 T 43N R 22W 3
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, Paul R. Bressette, in a field survey on September 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numerical data and symbols representing corner points.

- A. Description of original monument and accessories and/or subsequent restoration:
-4. Quarter Corner common to Sections 11 and 12. 1971: Frank Bray, RLS. Found iron pin as set by Marcus McNabb witnessed by: P.Pole N42W 39.0'; 24" Elm N16E 59.3'.
-5. Section Corner common to Sections 11, 12, 13 and 14. 1972: Frank Bray, RLS. Set 1/2" x 14" rebar witnessed by: 9" Balsam S55E 56.9'; 7" Balsam N78E 46.6'.
-6. Quarter Corner common to Sections 13 and 14. 1972: Frank Bray, RLS. Set 1" x 14" iron pin witnessed by: 5" B. Ash N48E 44.9'; 4" B. Ash S46E 48.8'.
3. North One-sixteenth Corner common to Sections 13 and 14. 1972: Frank Bray, RLS. Set 1/2" x 14" iron pin witnessed by: 5" B. Ash N64E 52.0'; 5" B. Ash N62E 44.8'.
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
-4. Found iron pin and elm NBT as described. Elm is a stump with scribing in lower face visible. Replaced iron pin with 1" iron pipe with plastic cap and witnessed.
-5. Found rebar and balsam NBT to NE as described. Replaced rebar with 1" iron pipe with plastic cap and witnessed.
-6. Found iron pin and NE NBT as described. Replaced iron pin with 1" iron pipe with plastic cap and witnessed.
3. Found iron pin and witnesses as described. Bearing recorded as N64E should be S64E. Replaced iron pin with 1" iron pipe with plastic cap and witnessed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 4 columns: 4.1"pipe w/plastic cap, K-5.1"pipe w/plastic cap, K-6.1"pipe w/plastic cap, 3.1"pipe w/plastic cap. Rows list monument types and bearings (e.g., Apple N68E 60.85', Pole N39W 38.85').



Paul R. Bressette Date 37270