

Robert Schmeling
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
DELTA
(County)

Located In: Corner Code ##

1. Public Land Survey T 43 N R 23 W G-11 & I-11
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

MAY 13 1994

Recorded
9:00 of _____ o'clock _____ AM In Liber 7 Page 399
William C. Thomas Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims G-11 [NW COR SEC 34] I-11 [NE COR SEC 34]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on FEBRUARY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
G-11 [NW COR SEC 34] MARTIN M. HALL, D.S. - 1853 - FIR POST (CEDAR 12°-S34°W-25 LINKS) (CEDAR 14°-N36°E-21 LINKS)
D.A. BROTHERTON - 1908 - STAKE IN PLACE - SET TAMERAC POST WITH NAILS N & S 33'
J.E. GINGRASS - 1912 - STAKE IN PLACE & BT STAKES N & S 33'
M.S. McNABB - 1913 - ORIGINALS GONE - ID BY STAKE IN PLACE & BT STAKES N & S 33'
M.D.O.T. - FOUND IP - SOUTH EDGE OF E-W COUNTY ROAD
- I-11 [NE COR SEC 34] MARTIN M. HALL, D.S. - 1853 - CEDAR POST (CEDAR 18°-N04°W-29 LINKS) (CEDAR 18°-S15°E-15 LINKS)
M.D.O.T. - 1955 - FOUND AXEL SHAFT IN PLACE

NOTED

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-11 [NW COR SEC 34] FOUND 1" IP ON SOUTH SHOULDER OF E-W COUNTY ROAD - ID CORNER MONUMENT FROM M.D.O.T. TIES TO SURVEY C/L OF STATE HWY M-35.
ACCEPTED AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

I-11 [NE COR SEC 34] FOUND AXEL SHAFT IN PLACE - ID CORNER MONUMENT FROM M.D.O.T. TIES FOR SURVEY OF STATE HWY. M-35. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-11 SET, OVER EXISTING IP, A BERNTSEN ALUMN MON WITH THE CAP STAMPED TO ID THE CORNER POSITION.
POWER POLE CHISELED "X" ON W END CONC X-PIPE SURVEY MONUMENT SIGN POST C/L E-W C.R.
S75°W 40.37' S65°E 80.72' SOUTH 2.1 (TO FACE) NORTH 12.4'
- I-11 DID NOT DISTURB EXISTING MONUMENT
CEDAR 9" CEDAR 9" SURVEY MONUMENT SIGN POST
S38°W 30.22' N50°E 51.82' S57°E 9.45'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG, UNLESS NOTED OTHERWISE.

Signed by M.P. Davis Date 5/6/94

Surveyor's Michigan License No. 16926