

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 & 44 N.R. 23, 24 W


Delta & Marquette COUNTY

DESCRIPTION OF CORNER Town Corner for Sections T 44 N R 24 W 36/31 T 44 N R 23 W
T 43 N R 24 W 1/6 T 43 N R 23 W

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 8-25-61

WITNESSES TO CORNER..... 6" Black Ash (S 36)(NBT) N 55° W 16 1/2 links



8" Cedar (S 31)(NBT) N 34° E 57 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement between Section Corners 1 mile south, 1 mile east and 2 miles north and 1/4 Corner 1/2 mile west.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 27, 1964
REGISTERED LAND SURVEYOR
Billy D. Buckler