

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**DELTA
Co.**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>18</u> T. <u>43</u> N ^N S ^S R. <u>23</u> W ^{XX}		A-6 - A-7
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-6 West 1/4 corner of Section 18 - Wood post, Birch 18-S22W-No dist. given
Maple 14-N13E- 4 lks.

A-7 S.W. section corner of Section 18 - Wood post, Fir 8-S25W-27 lks.
Tamarack 12-N63E-47 lks.
Tamarack 18-S71°E-27 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-6 Set M.P.O.L. between the N.W. and S.W. section corners of Sec. 18

A-7 Found Oliver Iron Mining Co. monument. This monument is not of record but it is very near a proportionate measurement from the S.W. section corner of Sec. 19 to the west 1/4 corner of Sec. 7. It is somewhat east of a straight line but the measurement east to the N.E. corner of Sec. 19 is longer than record so a straight line position would not fit as well. Witnessed monument as found. No evidence of original survey found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 7" cedar N27°W 4.2'	A-7 7" B. spruce N74°E 28.5'
8" cedar N59°E 25.5'	9" cedar N18°E 45.6'
4" cedar S58°E 11.1'	5" R. maple N49°W 9.4'
6" cedar S27°W 22.0'	8" cedar S69°E 35.6'

DNR monument

Oliver Iron Mining Co. monument
3" brass cap on 1 1/4" pipe

SIGNED BY _____

David B. Babbitt

DATE _____

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)