

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**DELTA  
CO.**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	19 T. 43 N. <del>XX</del> R. 23 <del>XX</del> W.	C-7, C-8, C-9
2. PROPERTY CONTROLLING IN SECTION	T. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- C-7 North East corner Section 19 - Spruce post, Spruce 11" - N67°E-37 lks.  
Spruce 11" - S41°W-15 lks.
- C-8 East 1/4 corner of Section 19 Cedar post, Hemlock 20"-N51°W-60 lks.  
W. pine 34"-S49°E-50 lks.
- C-9 S.E. section corner of Sec. 19 Fir post, Cedar 10" - N45°W - 31 lks.  
Y.birch 10" - S45°E - 32 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- C-7 Found Oliver Iron Mining Co. monument. This monument is not of record but local land owners have accepted it as being the true corner and its position is reasonable with other corners in the area. Witnessed monument as found.
- C-8 Found 1 1/4" pipe which appears to be the bottom section of an Oliver Iron Mining Co. monument with the brass cap removed. This pipe is not of record but it is very near M.P.O.L. between the NE and SE sec. cors. of Sec. 19 and has been accepted as the corner by local land owners. Witnessed pipe as found. No evidence of original survey found.
- C-9 Found Oliver Iron Mining Co. monument. This mon. is not of record but local land owners have accepted it as being the true corner and its position is reasonable with other corners in the area. Witnessed monument as found.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                               |                          |
|-------------------------------|--------------------------|
| C-7 4" cedar N78°W 15.1'      | C-9 5" Cedar S62°W 26.0' |
| 5" B. spruce N49°W 22.1'      | 16" Cedar S16°E 23.7'    |
| 6" B. spruce N67°E 26.4'      | 9" B. spruce N40°E 9.0'  |
| 9" B. spruce S35°W 26.4'      | 9" B. ash N66°W 34.9'    |
|                               |                          |
| C-8 15" W. spruce N26°E 29.9' |                          |
| 7" W. spruce S26°W 38.0'      |                          |
| 5" R. maple S 3°E 27.3'       |                          |
| 10" W. birch N79°W 18.0'      |                          |

SIGNED BY \_\_\_\_\_

David B. Babbitt

DATE \_\_\_\_\_

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)