

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY..... 7 T. 43 N. <del>XX</del> R. 23 <del>XX</del> W.		A-5
2. PROPERTY CONTROLLING IN SECTION..... 7 T. 43 N. <del>XX</del> R. 23 <del>XX</del> W.		10
3. MISCELLANEOUS PROPERTY IN SECTION..... T. S. R. E. W.		
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

**DELTA  
Co.**

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-5 South West Section corner of Section 7 - Wood post, Cedar 14 - S32W - 18 lks.  
Cedar 12 - N23E - 24 lks.

10 S 1/16 corner on west boundary of Sec. 7 - Not previously established

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-5 Set by single proportion between the west 1/4 corner of Sec. 7 and the N.W. section corner of Sec. 19. No sign of O.B.T.s.

10 Set M.P.O.L. between the west 1/4 corner and the S.W. section corner of Sec. 7

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: D.N.R. monument

A-5	8" Cedar	N44°W	10.7'		10	4" Cedar	North	15.7'
	5" Cedar	S43°W	18.4'			5" Cedar	N31°E	23.1'
	10" Cedar	N65°E	4.0'			5" Cedar	S60°E	19.2'
	9" Cedar	S54°E	19.5'			4" Cedar	S18°W	21.0'

SIGNED BY

*David B. Babbitt*

DATE

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: