

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

**DELTA
Co.**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T..... N. S., R..... E. W.	
2. PROPERTY CONTROLLING IN SECTION 19	T. 43 N. R. 23 XX S. R. 23 W.	9 - 14 - 16
3. MISCELLANEOUS PROPERTY IN SECTION.....	T..... N. S., R..... E. W.	
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9 East 1/16 corner on the E-W 1/4 line of Sec. 19 - not previously established
- 14 South 1/16 on east boundary at Sec. 19 - not previously established
- 16 East 1/16 corner on the south section line of Sec. 19 - not previously established

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9 Set M.P.O.L. between the ctr. of Section and the East 1/4 corner of Sec. 19
- 14 Set M.P.O.L. between the east 1/4 corner and the S.E. section corner of Sec. 19
- 16 Set M.P.O.L. between the south 1/4 corner and the S.E. section corner of Sec. 19

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: D.N.R. monument

- | | |
|-------------------------------|-------------------------------|
| 9 8" red maple S65°E 10.1' | 16 8" balsam fir N26°W 119.4' |
| 7" red maple S41°W 17.9' | 5" white birch N 1°W 83.4' |
| 3" balsam fir N70°W 23.9' | 6" balsam fir S 8°E 59.6' |
| 5" red maple N 5°W 9.0' | 8" b. spruce S34°W 96.2' |
| 14 4" tamarack N27°E 59.5' | |
| (dead) | |
| 4" tamarack(dead) N55°E 47.7' | |
| 8" balsam fir N 3°W 164.2' | |

SIGNED BY David B. Babbitt DATE 3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)