

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ T. _____ S., R. _____ E. W. | | |
| 2. PROPERTY CONTROLL- ING IN SECTION 19, T. 43 N. XX, R. 23 XX W. | | 1 - 3 - 10 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S., R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

**DELTA
Co.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1 West 1/16 on north boundary of Section 19 - not previously established
- 3 N 1/16 corner on the west sec. line of Sec. 19 - not previously established
- 10 S 1/16 corner on the west sec. line at Sec. 19 - not previously established

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 Set by single proportion to the G.L.O. record between the north 1/4 corner and the N.W. section corner of Sec. 19
- 3 Set M.P.O.L. between the W 1/4 corner and the N.W. section corner of Sec. 19
- 10 Set M.P.O.L. between the west 1/4 corner and the S.W. section corner of Sec. 19

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: D.N.R. monument

- | | |
|-----------------------------|------------------------------|
| 1 6" sugar maple West 19.6' | 10 4" balsam fir S50°E 25.8' |
| 7" red maple N50°E 24.9' | 10" tamarack S24°W 44.5' |
| 7" sugar maple N35°W 31.4' | 9" tamarack North 0.8' |
| 9" sugar maple S57°E 9.1' | 8" tamarack N46°E 14.8' |
| | |
| 3 4" cedar S55°W 35.8' | |
| 9" cedar N83°W 30.8' | |
| 5" red maple South 22.4' | |
| 5" red maple N56°E 12.4' | |

SIGNED BY: David B. Babbitt DATE: 3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)