

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY 19 T. 43 XX N. R. 23 XX W.		A-8 - B-8
2. PROPERTY CONTROLLING IN SECTION T. S. R. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION T. S. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**DELTA
Co.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B-8 Center 1/4 corner of Sec. 19 - not previously established

A-8 West 1/4 corner of Sec. 19 - Wood post; fir 8-S60W-25 lks.; B. ash 6-N69E-23 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-8 Set at the intersection of the N-S and E-W 1/4 lines of Section 19

A-8 Set M.P.O.L. between the N.W. and S.W. Sec. corners of Sec. 19. Found rusted off Oliver Iron Mining Co. mon. N12°W - 61.2' from this position but it is not of record and does not fit well with the N.W. and S.W. sec. corners of Sec. 19. It appears that it may have been set 2640 north of the erroneous Oliver Iron Mining Co. monument found near the S.W. sec. corner. No evidence of the original government survey was found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: D.N.R. monument

B-8 7" b. ash N51°W 22.0'
5" b. ash N42°E 27.0'
4" b. ash S50°E 5.0'
9" b. ash S22°W 39.1'

A-8 14" tamarack N75°W 41.6'
6" black ash N24°E 25.4'
5" black ash N88°E 9.6'
7" red maple S43°W 20.7'

SIGNED BY

David B. Babbitt

DATE

3-12-84

SURVEYORS MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: