

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>19</u>	T. <u>43</u> N. XX , R. <u>23</u> XX W.	B-7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA
Co.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

North 1/4 corner of Section 19 - Wood post, Spruce 10" - S7°E-26 lks.
Cedar 5" - N36°W-31 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set M.P.O.L. between the N.E. and N.W. Sec. Cors. of Sec. 19. We found an Oliver Mining Co. mon. stuck loosely in the ground without the usual pointed bottom section that their mons. have S46°E-75' from this position. It was very shallow in the ground and its position is not compatible with the N.E. and N.W. sec. cors. of Sec. 19. For these reasons I believe the Oliver Mining Co. mon. had been moved from where they set it. I, therefore, have set our mon. at the proportionate position between the two section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. monument

4" cedar	S 3°W	16.0'
6" cedar	S38°W	15.1'
4" cedar	N64°W	17.3'
7" cedar	N27°E	4.0'

SIGNED BY _____

David B. Babbitt

DATE _____

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)