

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY 19 T. 43 N. S., R. 23 E. W.		B-9 - A-9
2. PROPERTY CONTROLLING IN SECTION T. N. S., R. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S., R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA
Co.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 19 84, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-9 South 1/4 corner of Sec. 19 - Spruce post, tamarack 18"-N46°E-221ks.;
spruce 16"-S51°W-87 lks.
- A-9 SW Sec. corner of Sec. 19 - Wood post, B. ash 10-S35W-24 lks., spruce 12-N84E-4 lks.,
spruce 14-S3E-44 lks.

Marquette County Road Commission record 1948[±] "Oliver Iron Mining Company pipe w/brass cap. This pipe is set about 90 ft. too far north. Found an old post set correctly. B.T.s have fallen and badly decayed, but correspond with field notes."

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-9 Set by single proportion to the original survey record between the S.W. and S.E. section corners of Sec. 19. No sign of O.B.T.s.
- A-9 Set in line with old fence south and approximately 90' southerly of Oliver Iron Mining Co. monument as described in Marquette Co. Road Commission record. Could not find the post they describe or any sign of O.B.T.s but swamp calls, 1 ch. south, 5 chs. north and 1 ch. east all fit well. Measurements north-south and east also look good. The position of the Oliver Iron Mining Co. mon. is definitely not right.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: D.N.R. monument

B-9	7" balsam fir	N40°E	13.3'	A-9	7" black ash	S57°W	18.0'
	4" black ash	S12°E	20.4'		6" black ash	N 2°E	7.6'
	12" black ash	S62°W	22.9'		3" black ash	N58°E	18.7'
	3" black ash	N45°W	15.0'		5" black ash	N51°W	17.0'

SIGNED BY

David B. Babbitt

DATE

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)