

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—:	LOCATED IN—:	N. S., R.	E. W.	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____	_____	_____	_____
2. PROPERTY CONTROLLING IN SECTION	19	T. 43	N. <del>XX</del> R. 23 <del>XX</del>	5 - 8 - 6
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____	_____	_____	_____
4. LOT NO. _____, RECORDED PLAT _____				
5. PRIVATE CLAIMS _____				

**DELTA  
CO.**

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on March 9, 1984, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 8 West 1/16 corner on the E-W 1/4 line of Sec. 19 - not previously established
- 5 North 1/16 corner on the N-S 1/4 line of Sec. 19 - not previously established
- 6 NE 1/16 corner of Sec. 19 (center of the NE 1/4) - not previously established

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8 Set by single proportion between the west 1/4 corner and the center of Sec. 19
- 5 Set M.P.O.L. between the north 1/4 corner and the center of Sec. 19
- 6 Set at the computed center of Sec. 19 by closed traverse

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: D.N.R. monument

- |   |              |       |        |  |   |               |       |       |
|---|--------------|-------|--------|--|---|---------------|-------|-------|
| 8 | 4" tamarack  | N57°E | 17.0'  |  | 6 | 4" balsam fir | N20°W | 9.7'  |
|   | 7" cedar     | S58°E | 11.9'  |  |   | 8" red maple  | N62°E | 25.5' |
|   | 5" B. spruce | S66°W | 33.4'  |  |   | 5" balsam fir | S84°E | 6.5'  |
|   | 4" cedar     | N38°W | 13.5'  |  |   | 6" balsam fir | S45°W | 6.2'  |
|   |              |       |        |  |   |               |       |       |
| 5 | 10" cedar    | N 5°E | 51.95' |  |   |               |       |       |
|   | 5" cedar     | S66°E | 21.4'  |  |   |               |       |       |
|   | 8" cedar     | S10°E | 45.05' |  |   |               |       |       |
|   | 17" w.pine   | N78°W | 42.35' |  |   |               |       |       |

SIGNED BY

*David B. Babbitt*

DATE

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)