

JAN 25 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Dec 28, 1999

John Schmeiding
Chairman

For corners in

DELTA (County)	Located in:	Corner Code #
1. Public Land Survey	T 43 N R 20 W T 44 N R 20 W T 43 N R 20 W T R	I-1 SAME I-13 CORNER I-2
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

01-04-00
2:00 O'CLOCK PM
LIBER 9 PAGE 184
Walter S. Thomas

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I-1 [NW COR SEC 2] I-2 [W1/4 COR SEC 2]

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1									●				
2	6		5			4			3	●	2		1
3													
4	7		8			9			10		11		12
5													
6	18		17			16			15		14		13
7													
8	19		20			21			22		23		24
9													
10	30		29			28			27		26		25
11													
12	31		32			33			34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-1 [NW COR SEC 2] JOHN BURT, D.S.-1841-WOOD POST-(TAMARACK 04" N50°E 81 LINKS)(TAMARACK 04" N53°W 47 LINKS) A.MERRYWEATHER, D.S.-1849-WOOD POST IN PLACE (BIRCH 06" S60°E 07 LINKS)(BIRCH 09" S70°W 18 LINKS) G.ASHER U.S.F.S.-1983-L.7 OF LCR'S PG. 258-SET, BY PROPORTIONATE MEASUREMENT 2-1/2"X48" GALVANIZED I.P. W/A 3-1/4" BRASS CAP STAMPED TO ID THE CORNER POSITION. [S.MAPLE 05" N54°E 66.5'] [W.PINE 05" S33°E 28.90'] [RED PINE 10" S88°W 210.3'] [RED PINE 14" N54°W 302.9'] [4" X 4" CEDAR POST NORTH 3.8']
- I-2 [W1/4 COR SEC 2] A.MERRYWEATHER, D.S.-1849-WOOD POST (HEMLOCK 10" N30°E 12 LINKS)(BIRCH 12" S45°W 08 LINKS) NO RECORD EVIDENCED OF CORNER RECOVERY AND/OR SUBSEQUENT MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-1 [NW COR SEC 2] FOUND IN PLACE A 2-1/2" IRON PIPE W/A 3-1/4" BRASS CAP ATTACHED AND STAMPED TO ID THE CORNER POSITION. ID EXISTING MONUMENT FROM 4" CEDAR POST BY MENTIONED AT L.7 OF LCR'S PG.257. ALL OTHER ACCESSORIES HAVE BEEN DESTROYED. ACCEPTED EXISTING MONUMENT AS BEING A CAREFULL AND FAITH-FULL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
- I- [W1/4 COR SEC 2] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION ON LINE WITH AND AT SINGLE PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNERS 1/2 MILE TO THE NORTH AND SOUTH.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 DID NOT DISTURB EXISTING MONUMENT.
POPLAR 06" N60°W 30.46'
POPLAR 05" S46°W 30.28'
MAPLE 08" N82°E 48.60'
4" X 4" CEDAR SIGN POST NORTH 3.58' (TO FACE)
- I-2 SET A BERNTSEN A1NB30 ALUM MONUMENT W/A 3-1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 06" N67°W 30.61'
SPRUCE 05" N46°W 41.58'
MAPLE 08" S37°E 16.76'
MAPLE 11" S32°W 68.91'
SURVEY MONUMENT SIGN POST NORTH 1.29' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/20/99
Surveyor's Michigan License No. 16926