

**SURVEY &
REMONUMENTATION
APR 07 1995
COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Dickinson
(County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Section 7 | T <u>39N</u> R <u>28W</u> | <u>A-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
 HONOLAND COUNTY
 1994 DEC -9 PM 3:44
RECORDED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
 Section corner to 7 and 18, T39N, R28W and 12 and 13, T39N, R29W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on November 7, 1994
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Township boundary by H. Brevoort, D.S. Original bearing trees: elm 14" - S20°W, 22 links; fir 12" - N57°W, 32 links; lynn 6" - N74°E, 41 links; fir 6" - S35°E, 59 links. WEPCO diagram of Section 18 (no date) indicates iron pin in concrete at corner position.

1981 - Plat of survey by Robert Perkins, RLS, shows corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pin with blazed lines running east and west and a cut line running south. I am accepting the iron pin as marking the corner position by use and acceptance. The iron pin has obviously been used for a number of years and is shown on several surveys of record.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD
1-23-95
ROP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Dickinson County monument at position of 1" iron pin and established following references: Existing 9" basswood B.T. - N42°E, 20.42 feet; existing 9" basswood B.T. - S03°E, 20.34 feet; existing 12" basswood B.T. - S61°W, 23.58 feet; existing 13" aspen B.T. - N86°W, 25.23 feet; set carsonite witness post - North - 1.5 feet.



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/8/94