

SURVEY & REMONUMENTATION COMMISSION

For corners in APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 DICKINSON COUNTY
 1034 DEC -9 PM 3:44
 RECORDED

Located In: _____ Corner Code #/ # _____

1. Public Land Survey Section 7 T 39N R 28W _____ B-5 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
 1/4 corner to Sections 7 and 18

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	•												
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on November 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1849 - Township subdivision by James H. Mullett, D.S. Original bearing trees: aspen 2" - N20°E, 12 links; aspen 2" - S30°E, 13 links.

Corner shown on Bremner Addition to Village of Loretto.

Corner shown on 1934 Dickinson Co. Rd. Commission R.O.W. map.

WEPCO diagram of Section 18 indicates iron pin in concrete at corner position (no date).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pin in concrete as called out above. Accepted iron pin as marking the corner position based on its longevity and general use and acceptance on record surveys, plats and by local residents.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95
ROB P
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Dickinson County aluminum monument at position of 1" iron pin and established following references: 11" jack pine - N46°E, 106.71 feet; 5" jack pine - S06°W, 32.61 feet; 5" spruce - S44°W, 2.32 feet; 4" jack pine - N87°W, 50.71 feet; set carsonite witness post - north 2.0 feet.

Signed by John R. Garske Date 12/8/94
 Surveyor's Michigan License No. 28410



Index 2 B-5 Page 112