SURVEY & AFRON 1995

LAND CORNER RECORDATION CERTIFICATE

	LAND COMM	EN NECONDATION CEITHINGNI	-								
For corners in COMMISSIO	Filing Requir	ement of Act 74, Mich. P.A. 197	0		걸						
Dickinson	Located In:	Corner Code ≠		K.	ZŽ			\Box			
(County)				2	113		co to	$\dot{\circ}$			
1. Public Land Survey Section	8 т <u>39N в 28W</u>	C-5		. ** . 	ja Ja			JU)		
	T R			4	224			Ü			
	T R			<u>p</u> .	H		ယု		i r		
	T R			3	TO CO		<u></u>	U	,		
	T R T						+Bor**				
			egister		Daa	4a C1	amn í	. Eila	Num	har	
	T R		eāizīci	UI	Deed	12 GI	amp e	, rne	MARTIN	<u></u>	
	-										
4. Lot No, Recorde			д	В	c	D E	E F C	з н	l J	κι	. м
5. Private Claims	2 17 5 10		- ,[
Section corner to 7, 8	3, 1/ & 18		3	Ĺ				Ľ			İ_
			4	_ [_10	1	\bot	12-
ı. <u>John R. Garske</u> , in a fi	ield survey on October	24 and November 7 . 19 . 94	5			Ľ	Ľ	_ <u>Ľ</u>		_ _	Ĺ
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned					L	17	_16	15	1-14		13
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land										<u> </u>	1_
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5					1_	20	_21	 22	23		24_
above were in conformance with the rule	les of the Michigan Board	of Land Surveyors or by a Decree of a	9	1		-			1-1	_ _	1
Court of Law; established, re-estable expressed below:	lished, monumented, re-	monumented, recovered, found as	10	 —30-	1	29	28	27	26	_ _	25
· ·	all in the same town a	nd range may be recorded	11	1	_ļ_	1		1	 	 	1_
NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.					1	32	33	34	35		J 36
-		•	13		_L_						<u> </u>
A. Description of original monume	ent and accessories an	d/or subsequent restoration:									
		was a state of D.C. O. C. C. and D.T.	Ca	400	12"	N	25°₽	17			

- 1849 Township subdivision by James H. Mullett, D.S. Original B.Ts: Cedar 12" N35°E, 17 links; cedar 10"- S46°E, 32 links.
- 1915 Dickinson Co. Rd. Commission map shows C.II. Found a 2" stake w/tack.
- 1934 Dickinson Co. Rd. Commission R/W map shows corner lying 980 feet south of road centerline and 2615.3 fect east to 1/4 corner.
- 1950 WEPCO map shows iron pin at corner.

WEPCO section diagram of unknown date indicates a well point at section corner.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" well point on N-S fence line. Blue line running north, south, east and west from well point. Three existing recently blazed bearing trees were also found facing the well point. Accepted well point as corner position. Given the record chain of evidence and the use and acceptance of the existing corner location. I am accepting the well points marking the correct corner position.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFIC:AL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Replaced well point with aluminum Dickinson County monument and established the following references: existing 6" cedar B.T. - N03°W, 8.46 feet; existing 6" cedar B.T. - S27°E, 25.29 feet; 5" cedar - S64°W, 37.60 feet; existing 4" cedar - N49°W, 20.30 feet; set carsonite witness post -East, 2.0 feet.

Surveyor's Midhigan License No. _

LAND VEYORS, JAN. 28, 1971 REVISEO MAY 14, 1975

REVISED JAN., 1983

MIC

JOHN R. GARSKE LAND SURVEYOR No. 28410

Liber 2