

SURVEY &
 REMONUMENTATION
 APR 07 1995
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corner in _____
 Dickinson
 (County) Located In: _____ Corner Code # _____

1. Public Land Survey Section 20 T 39N R 28W C-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
 MICHIGAN COUNTY
 1994 DEC -9 PM 3:44
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
 Section corner to 19, 20, 29 & 30

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 25 and 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1849 - Township subdivision by James H. Mullett, D.S. Original bearing trees: cedar 12" - N70°W, 13 links; cedr 12" - S52°E, 08 links.

1934 - Dickinson Co. Rd. Commission H.L. Wagner found an iron pipe on N-S fence line.

WEPCO line map indicates iron pipe at section corner (no date on map).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 1/2" iron pipe protruding 18" above the ground on a N-S fence line & 2 existing cedar bearing tree stumps scribed NBT. I am accepting the pipe as marking the corner position based on Wagner's 1934 notes found in the Dickinson Co. Rd. Commission Office. This pipe has been used and accepted for many years by local surveyors, residents and the Road Commission.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95
ROPP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Drove existing pipe down and set Dickinson Co. monument consisting of a 3/4" diameter x 36" long aluminum rod with a 2 1/2" diameter stamped aluminum cap inside existing pipe. Established the following references: 6" cedar - N21°E, 36.11 feet; 5" balsam - S87°E, 25.56 feet; 4" black spruce - S65°W, 23.14 feet; 10" cedar - N32°W, 30.31 feet; set carsonite witness post - North - 1.0 foot.

Signed by John R Garske Date 12/8/94
 Surveyor's Michigan License No. 28410

