

**SURVEY & REMONUMENTATION**

APR 07 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Dickinson  
 (County)

Located In: \_\_\_\_\_ Corner Code =# \_\_\_\_\_

1. Public Land Survey Section 17T 39N R 28W \_\_\_\_\_ D-5 \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section          S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_  
    1/4 corner to 8 and 17

REGISTER OF DEEDS  
 OFFICE OF COUNTY  
 CLERK  
 1004 DEC - 9 PM 3:44  
**RECORDED**  
 Register of Deeds Stamp & File Number

I, John R. Garske, in a field survey on October 24 and November 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1849 - Township subdivision by James H. Mullett, D.S. Original B.T.s: Maple 4" - N55°E, 29 links; Birch 4" - S80°E, 22 links.

1915 - Dickinson Co. Rd. Commission C.I.I. found no trace of corner or B.T.s, so he used a fence corner as 1/4 cor.

1934 - Dickinson Co. Rd. Commission R.O.W. map shows corner with distances of 2656 feet east and 2615.3 feet west to known corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At approximate intersection of remnants of ancient fences running east and south, I found a piece of a squared stake leaning against an old pine stump just N.E. of a 12" aspen with a location poster on it. Just south of stake I found small post hole with rotted post point in it. This position checks well with GLO swamp calls east and west. Accepted post point as best available evidence.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95  
R.O.P.  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Dickinson Co. aluminum monument at location of post point and established the following references: 11" W. pine - N17°E, 57.03 feet; 6" maple - S82°E, 41.13 feet; 5" maple - S14°E, 45.02 feet; 10" W. pine - S79°W, 42.93 feet; set carsonite witness post - South, 1.71 feet.

Signed by John R. Garske Date 12/8/94  
 Surveyor's Michigan License No. 28410



*Liber 2 D-5 page 117*