

**SURVEY & REMONUMENTATION COMMISSION**

APR 07 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Dickinson  
 (County)

Located In: \_\_\_\_\_ Corner Code ##

REGISTER OF DEEDS  
 DICKINSON COUNTY  
 1000 W. WASHINGTON

RECORDED  
 1994 DEC -9 PM 3:44

Register of Deeds Stamp & File Number

- 1. Public Land Survey Section 20T 39N R 28W D-7  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_  
    1/4 corner Sections 17 and 20

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John R. Garske, in a field survey on October 24 and 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1849 - Township subdivision by James H. Mullett, D.S. Original bearing trees: Y. pine 20" - N75°W, 27 links; W. pine 10" S39°W, 21 links.

Keweenaw Land Association Ltd. Township diagram indicates pipe at 1/4 corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" water pipe with a coupling on top. Blazed lines are running east and west, with three existing bearing trees facing the corner. The corner has obviously been used and accepted for many years and I am accepting the pipe as marking the true corner position.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON 1-23-95  
ROP  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set aluminum Dickinson County monument at position of water pipe and established the following references: existing 11" aspen B.T. - N20°E, 4.70 feet; existing 6" oak B.T. - S66°E, 28.90 feet; existing 7" oak B.T. - S25°W, 34.83 feet; 9" basswood in clump of 6 - N75°W, 55.22 feet; set carsonite witness post - North - 1.0 foot.



Signed by John R. Garske Date 12/8/94  
 Surveyor's Michigan License No. 28410