

**SURVEY &  
REMONUMENTATION**

DEC 18 1995

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1995 NOV 21 AM 11:27

For corners in Dickinson Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 39N R 28W E-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER OF DEEDS  
 DICKINSON COUNTY  
 REGISTERED

**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert F. Perkins, in a field survey on Oct. 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-6 West 1/2 Corner, Section 16  
 Post J.H. Mullett, D.S. 1849  
 Original Bearing Trees  
 Beech 10" S67°W (M.B.) 33 Lks.  
 Beech 18" N20°E (M.B.) 30 Lks.


ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-26-95  
RFP  
 COUNTY REPRESENTATIVE

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-6 No Evidence of Original Corner or Accessories Found.  
 Found 1 1/2" Iron Pipe at Fence Corner as referred to in Dickinson County Road Commission Records.  
 Corner Researched in 1994.  
 Distance checks North to Section Corner and East to Center Section per G. Hellberg Survey (1897).  
 Accepted existing Pipe as Best Available Evidence.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-6 Replaced above Pipe with 2 1/2" Stamped Dickinson County Remonumentation Monument.  
 New Witnesses  
 Beech 3" S48°W (M.B.) 29.20'  
 Beech 5" S30°E (M.B.) 12.90'  
 Ironwood 3" N64°W (M.B.) 29.57'  
 Maple 5" N13°E (M.B.) 8.76'  
 Carsonite Marker placed ±1' West.



Signed by Robert F. Perkins Date Nov. 7, 1995

Surveyor's Michigan License No. 12027

186