

SURVEY & REMONUMENTATION

APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dickinson
 (County)

COMMISSION

Located In: _____ Corner Code E-8

- 1. Public Land Survey Section 20 T 39N R 28W E-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
DICKINSON COUNTY
RECORDED
1994 DEC -9 PM 3:44
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
 1/4 corner Sections 20 & 21

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John R. Garske, in a field survey on October 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by James H. Mullet, D.S., in August 1849. Set post. Original bearing trees: beech 6" - N6°W, 16 links; fir 3" - S68°W, 20 links.

1937 - Dickinson Co. Rd. Commission R.O.W. map shows a distance of 2700.8 feet south to section corner and a distance of 2609.4 east to the center of Section 20.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" iron pipe with three existing bearing trees. A line running north-south has been recently surveyed. Corner is approximately 200 feet south of railroad tracks. The corner has been used and accepted in several surveys of record. Accepted the iron pipe as marking the true corner position.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95
R. B. P.
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Drove a Dickinson County aluminum monument inside existing 1/2" pipe. Established following references: carsonite rail - North, 1.5 feet; 9" W. pine (existing) - N26°E, 36.37 feet; 8" W. pine (existing) - S85°E, 35.85 feet; 9" W. pine (existing) - S26°E, 45.62 feet; 7" W. pine - N35°W, 50.57 feet.



Signed by John R. Garske Date 12/8/94
 Surveyor's Michigan License No. 28410

Liber 2 E-8 Page 122